



## City of Prince Albert

Public Works Department  
1084 Central Avenue  
Prince Albert, SK S6V 7P3  
Phone: (306) 953-4900  
Fax: (306) 953-4915

June 26, 2025

### 20 Street East (6-7 Avenue) – Watermain Relining

The City of Prince Albert Public Works Department would like to advise residents of the upcoming underground utility work on 20<sup>th</sup> Street East between 6<sup>th</sup> and 7<sup>th</sup> Avenue. The work includes the relining of the existing 1947 Cast Iron Watermain (highlighted in **blue**) with a structural liner, bringing the main to a like new condition without the need to excavate the entirety of the pipe length. The relining work requires excavation of pits at each end of the block (highlighted in **orange**) to feed the structural liner through the main. In conjunction with the watermain relining a 38-meter section of watermain will be conventionally excavated and replaced with a new 200mm PVC watermain (Outlined in **red**). The project will end with paving and select concrete repairs on the block. Residents can expect an additional notice to be delivered prior to paving and concrete repairs taking place.

1. **Project timeline:** July 2<sup>nd</sup> to August 15<sup>th</sup>, weather permitting.
2. **Impacted Areas:** Watermain relining will take place along the pipe segment highlighted in **blue**. You are receiving this letter because you either reside within the construction zone or within a 30-meter radius. The properties that will have their water impacted throughout the duration of the project are outlined in **blue**.
3. **Water Services:** To ensure that you continue to receive water throughout the project, the City will be providing above ground water services connected to your outside tap. The City will be inspecting the taps to ensure that your outside tap is functioning and is not a frost-free tap. If it is a frost-free tap, the City will replace it and reinstate it after construction completion. Your shutoff valve located within your house will also have to be in good working condition.
4. **Water Meters:** To ensure that water does not backflow from your house to the main while it is being relined, your water meters will have to be disconnected. You will, for the project duration, be receiving your water through your outside tap. The Contractor will be completing the water meter disconnections between **July 2<sup>nd</sup>** and **July 8<sup>th</sup>**. This will require you to provide access to the contractor. (Bylaw No 37 of 2017). Failure to allow access will result in your property not having water during the relining project. The meter will be reinstated after the project is completed.
5. **Limited Driveway and on-street parking access:**
  - There will be parking restrictions on the north and south side of the street throughout the duration of this project. No Parking signs will be placed on the boulevard when on-street parking is restricted.

6. **Traffic:** The zone highlighted in **red** will not be passable for portions of this project. During this time access to 6<sup>th</sup> Avenue East will be maintained on 21<sup>st</sup> Street East. Driveway access for residents in this area will not be possible during the conventional watermain replacement portion of this project.
7. **Garbage and Recycling Pick-up** will continue as scheduled. Place your bins on the sidewalk instead of the street.
8. **Landscaping and Trees:** 1 Tree will be removed to facilitate the completion of this project (Highlighted in **green**). The Forestry division will plant a new tree in this location following the project. Any landscaping impacted during this project will be restored following paving.

If you require further information with respect to this matter, please do not hesitate to contact Public Works at (306) 953-4884. For more information on this project or any other capital projects throughout the city, please visit [www.citypa.ca/capital-projects/](http://www.citypa.ca/capital-projects/).

Yours truly,

**Evan Hastings, B.Sc., C.E., EIT**  
Capital Projects Manager



# IMPORTANT NOTICE