

1.0 FIRES

- .1 Fires and burning of rubbish on site will not be permitted.

2.0 DISPOSAL OF WASTES

- .1 Burying of rubbish and waste materials on site is not permitted.
- .2 Disposal of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers, is prohibited.

3.0 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .2 Pumping of water containing silt in suspension into waterways, sewer and drainage systems prohibited.

4.0 SITE CLEARING AND PLANT PROTECTION

- .1 Protect trees and plants on site and adjacent properties where indicated.
- .2 Protect roots to drip line during excavation and site grading to prevent disturbance or damage. Avoid unnecessary traffic, dumping and storage of materials over root zones of protected trees.
- .3 Minimize stripping of topsoil and vegetation.
- .4 Restrict tree removal to those designated by Engineer.

5.0 WORK ADJACENT TO WATERWAYS

- .1 The Contractor's operation of construction equipment in waterways shall meet all Provincial and Federal Regulations. It shall be the Contractor's responsibility to secure all approvals.
- .2 Do not use waterway beds for borrow material.
- .3 Do not dump excavated fill, waste material or debris into waterways.

END OF SECTION